BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-57

Name of Work:-Construction of RCC drains at Mahalakshmi Layout in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHUMIREDDY DAMODAR REDDY	
				Rate	Rate in Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	116.85	210.20	Rupees Two Hundred Ten and Paise Twenty Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.3 of PWD SR 2018-19	Cum	18.45	4542.82	Rupees Four Thousand Five Hundred Forty Two and Paise Eighty Two Only
3	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 18, Item No. 4.48, PWD SR 2018-19	Cum	38.75	4847.34	Rupees Four Thousand Eight Hundred Forty Seven and Paise Thirty Four Only
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 Page No. 18 / Item No. 4.46.2, PWD SR 2018-19	Tonne	2.32	63188.13	Rupees Sixty Three Thousand One Hundred Eighty Eight and Paise Thirteen Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHUMIREDDY DAMODAR REDDY	
				Rate	Rate in Words
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No. 16 / Item No. 4.31 PWD SR 2018-19	Sqm	295.20	318.76	Rupees Three Hundred Eighteen and Paise Seventy Six Only
6	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.6 PWD SR 2018-19	Cum	3.69	4827.75	Rupees Four Thousand Eight Hundred Twenty Seven and Paise Seventy Five Only
7	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge - Data rate	Sqm	98.82	1963.08	Rupees One Thousand Nine Hundred Sixty Three and Paise Eight Only

B. Damodhar Reddy

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.